Project Location

I-95 corridor between Exit 16 in Norwalk and Exit 17 in Westport



Purpose and Need:

- Enhance safety
- Maintain "state of good repair"
- Be consistent with other previous construction throughout the corridor
- Project 102-295 DOES NOT include any new / additional lanes or other provisions to increase the capacity of I-95

Construction Information:

- Smart Work Zone Technology
- Inform the Public of Construction Closures/ Detours and Impacts
- During peak hours:
 - Maintain existing number of lanes in each direction
 - Reduced lane and shoulder widths
 - Implement lane shifts as necessary

Off-peak periods:

- Lane closures
- Temporary (overnight) ramp closures
- Short duration (10-15 Min) stoppages

Planned Improvements:

- Upgrade Roadway to Current Standards
 - Install concrete median barrier
 - Increase shoulder widths to 12' where possible
 - Replace existing guiderail
 - Install new highway illumination
 - Upgrade incident management system
 - Extend Interchange 16 northbound on-ramp

Rehabilitation of Bridges

- Full replacement of Bridge over Saugatuck Avenue
- Maintenance repairs on Bridge over Franklin Street and Bridge over Saugatuck River
- New Drainage on I-95 to Address Deficiencies & Highway Flooding
- Enhance Rideability
- Reconstruct & Expand Interchange 16 Park & Ride Lot
- Stormwater Quality Treatments

Contact Information

Website: i95norwalkwestport.com

Email: i95norwalkwestport@gmail.com Twitter: @i95norwest Resurfacing and Median Reconstruction Project No. 102-295





- Existing Length: 100'
- Does not meet current design standards
- Extended Length: 1050'
- Meets current design standards
- Improves driver safety



Contact Information

Website: i95norwalkwestport.com

Email: i95norwalkwestport@gmail.com Twitter: @i95norwest

SCAN ME

For additional information and updates,

visit our website:

High crash frequency